

**SECTION 15:**  
**INSPECTIONS, TESTS, AND SYSTEM CERTIFICATION FOR**  
**SPECIAL EXTINGUISHING SYSTEMS**

15.1 **Final Acceptance Test.** The installer shall pre-test all fire extinguishing systems **BEFORE** the final acceptance test.

15.1.1 **Procedure.** The AHJ shall witness a test of the fire extinguishing system as designed and approved. The installer shall provide all the test equipment needed. The installer shall test all initiating devices, audible appliances, visual appliances, and reset devices before the final acceptance test by the AHJ.

15.1.2 **Documentation.** The contractor shall provide the AHJ with a copy of the Test Certificate at the time of the final acceptance test. This document shall be required before the AHJ will sign any forms approving the system.

15.2 **Tests and Inspections.** Certified contractors shall perform tests and inspections for special extinguishing systems. The test and inspection shall comply with the most current edition of applicable NFPA standard(s). The contractor shall submit the test and inspection report to the AHJ in a format acceptable within thirty (30) days of completion of the test.